

IPRO 336: Architectural




View of Green House




View of Green House



Interior View




Roof Section



Roof Plan



Topic	Item	Size	Unit	Unit cost (\$)	Total Cost (\$)	
Structural Material	Frame	Cold Frames	20'W x 40'L x 18"	2	\$3,000	\$6,000.00
			20'W x 60'L x 18"	1	\$5,500	\$5,500.00
			20'W x 72'L x 18"	2	\$4,000	\$8,000.00
						\$17,500.00
	Concrete Floor	Foundation of Greenhouse	6"	110 sq'±	\$95	\$10,450.00
		Total				\$10,450.00
	End Walls - Covering	Triple-Wall Polycarbonate Sheets	4' x 12'	22	\$262.38	\$5,772.36
			4' x 12'	6	\$135.20	\$811.20
	Heating	Cross-Linked Polyethylene Pipe	3/4"	3000 ft	\$0.55	\$1,650.00
		Floor Heating/Hydronic Thermostats			\$132.95	\$265.90
Environmental Systems	Reflective / White Poly		6	\$454.69	\$2,728.14	
	Total				\$4,644.04	
Cooling and Ventilation System	Industrial Circulating Fans	24"	14	\$195.00	\$2,730.00	
	Two-Speed, 14,000-CFM Cooling Fans	42"	4	\$387.50	\$1,550.00	
	Polycarbonate Vent Window	40" x 40"	5	\$135	\$675.00	
	Total				\$4,955.00	
	Watering System	3-Zone Sprinkling System		10	\$67.95	\$679.50
Rotomax Sprinkler Assembly			10	\$14.95	\$149.50	
End Drain			10	\$5.59	\$55.90	
End Fitting			10	\$1.39	\$13.90	
Garden Hose		50'	3	\$59.25	\$177.75	
Lighting	Garden Hose	75'	2	\$77.98	\$155.96	
	Total				\$1,332.51	
Energy Efficient High Bay Fixtures		48"H	25	\$1.4	\$2,850.00	
	Total				\$2,850.00	
Controllers/Automation	Ventilation and Humidity Controllers		2	\$205.95	\$411.90	
	Total				\$411.90	
Total Cost					47315.01	



Structural Materials

This material has a lot of advantages listed below:

- Clear, UV-resistant sheets are lightweight, easy to handle and to install.
- Tough, scratch-resistant material resists 90% light transmission, over other years of use.
- Diffused light transmission reduces sudden fluctuations in temperature that could be dangerous to your flowers or vegetables.
- Superior insulating qualities for better heat retention saves you money on energy consumption.
- 30 years of guaranteed light transmission.
- Flame retardant and virtually no condensation, providing manufacturer's recommendations are followed.

Frames

Greenhouse frames range from simple to complex, depending on the magnitude of the designer and engineering requirements. This design employs a simple rigid frame with a curved roof.

Rigid frame

The rigid frame structure has vertical sidewalls and rafters for a clear span construction. In this greenhouse the frames are going to have a curved roof.

Covering

It was decided that the most efficient material to be used in this greenhouse would be a Triple-Wall Polycarbonate (10mm), as shown in the following picture:

This material has a lot of advantages listed below:

Triple-Wall Poly Polycarbonate offers a 30% better insulation factor over twin-wall.

- Clear, UV-resistant sheets are lightweight, easy to handle and to install.
- Tough, scratch-resistant material resists 90% light transmission, over other years of use.
- Diffused light transmission reduces sudden fluctuations in temperature that could be dangerous to your flowers or vegetables.
- Superior insulating qualities for better heat retention saves you money on energy consumption.
- 30 years of guaranteed light transmission.
- Flame retardant and virtually no condensation, providing manufacturer's recommendations are followed.

The only disadvantages for using such material are mostly aesthetic issues, suggesting that glass greenhouses are more pleasing.

Foundations and Floors

Since this greenhouse is located on the roof, the existing roof foundation is 8" of concrete and 6.5" of rigid insulation. One foot of concrete needs to be added to order heat the existing roof. Roof drainage will be added and can be drilled to drain the excess water from the plant's watering system, however with the addition of the foot of concrete a new system can be devised to better suit the greenhouse design. The new system will be linked to the old system. A slope of this system is shown in the roof drainage plan. Also a floor heating system could be used and placed under the concrete bed in order to provide the heating requirements.

Environmental Systems

Greenhouses provide a shelter and a suitable environment is maintained for plants. The sun is our best source for heat. However more systems need to be used in order to maintain the best environment and to obtain the best possible results from a greenhouse. This is done by using heaters, fans, thermostats, and other equipment. Several options were suggested for implementation in the greenhouse. The chosen results are what thought to be the most efficient, and reliable.

Heating

The heating requirements of a greenhouse depend on the desired temperature for the plants grown, the location and construction of the greenhouse, and the local outside ground area of the structure. As much as 25 percent of the daily heat requirement may come from the sun, but a highly insulated greenhouse structure will need a great deal of heat on a cold winter night. The heating system must be designed to maintain the desired day or night temperature.

Heating systems can be fueled by electricity, gas, oil, or wood. The heat can be distributed by forced hot air, radiant heat, hot water, or steam. The choice of a heating system and fuel depends on what is available, the production requirements of the plants, cost, and individual choice.

The formula used for finding the overall heat loss in the greenhouse, Q_h:

$$Q_h = \frac{A_1 T_1 + A_2 T_2}{R_1 + R_2} (T_1 - T_2) (C_1 V_1 / C_2 V_2)$$

Q_h - Heat loss used to determine the minimum size of heater or boiler required to maintain the inside design temperature, (Btu).

A₁, A₂ - Surface Area, (sq. ft.)

R₁, R₂ - Thermal Resistance of Each Component, (°C/M), Table 1

K₁ (Thermal resistance of glazing material) = 0.472 U-value for triple polycarbonate material.

K₂ (Thermal resistance of construction material) = 7.35 (0.4 for 8" thick concrete and 7.15 for 7.5" polystyrene foam).

T₁ - Inside / Temperature, (Indoor Temperature, °C).

T₂ - Outside Temperature, (Indoor Temperature, °C).

The temperature difference measured for inside temperature is 4 °C, and outside temperature ranging from -14 °C to 20 °C. Also, inside temperatures of 20 °C and 10 °C were compared to an outside temperature of 20 °C. Tables with the required data are provided below.

F₁ - Construction Factor = 0.7, for triple polycarbonate wall

F₂ - System Description, (C/W) = 1, radiation or convection near ground or below benches.

F₃ - Wind Factor

This value was provided by comparing the temperature differences calculated at a steady wind velocity of 25 mph.

Zone AAB

A ₁	A ₂
11,148	23,393
11,148	11,148
11,148	11,148
11,148	11,148

Zone ABC

A ₁	A ₂
11,148	23,393
11,148	11,148
11,148	11,148
11,148	11,148

Zone DDE

A ₁	A ₂
11,148	23,393
11,148	11,148
11,148	11,148
11,148	11,148

Zone EEE

A ₁	A ₂
11,148	23,393
11,148	11,148
11,148	11,148
11,148	11,148

Total heat loss:

Q_h = 105,120 Btu/hr (at 20 °C indoor temperature)

Q_h = 105,120 Btu/hr (at 10 °C indoor temperature)

Q_h = 105,120 Btu/hr (at 20 °C indoor temperature)

Ventilation and Cooling

Ventilation is the exchange of inside air for outside air to control temperature, remove moisture, or replace carbon dioxide (CO₂). In most ventilation systems can be used.

Natural ventilation uses roof vents on the ridge and side wall vents (lowers). Warm air rises and creates currents to escape through the top, drawing cool air in through the sides. This is a good system for spring and fall seasons when the outside temperature is not too hot.

The system that will be employed in this design is mechanical ventilation, which uses an exhaust fan to move air out one end of the greenhouse while outside air enters the other end through motorized inlet louvers. Exhaust fans should be used to exchange the total volume of air in the greenhouse each minute.

The total volume of air in a medium to large greenhouse can be estimated by multiplying the floor area by the average height of air in a greenhouse. A small greenhouse less than 5,000 ft³ in volume should have an exhaust fan capacity estimated by multiplying the floor area by 12.

The capacity of the exhaust fan should be selected at one-eighth of an inch static water pressure. The static pressure rating depends on an air resistance through the louvers, fans, and greenhouse and is usually shown on the fan selection chart.

An exhaust fan ventilation system may be used in a greenhouse. Small greenhouses need the larger amount. However, in larger greenhouses, the fan should be selected to provide the larger amount of air movement. Operate the fans continuously during the winter. Turn these fans off during the summer when the greenhouse will need to be ventilated.

Small fans with a cubic-foot-per-minute (CFM) air moving capacity equal to one-quarter of the air volume of the greenhouse are sufficient. For small greenhouses (less than 600 ft³ long), place the fans in diagonally opposite corners but not from the ends and sides. The goal is to create a circular (oval) pattern of air movement. Operate the fans continuously during the winter. Turn these fans off during the summer when the greenhouse will need to be ventilated.

The fan in a forced-air heating system sometimes can be used to provide continuous air circulation. The fan must be wired to an on/off switch so it can run continuously, separate from the thermostatically controlled burner.

The total air volume of the greenhouse is about: V = 72,000 ft³.

of that volume is about: v = 18,000 ft³.

The total number of fans needed to keep this greenhouse properly ventilated is fourteen circulating fans that will provide 1,800 CFM, and four cooling fans (4CFM).

The total number of fans needed to keep this greenhouse properly ventilated is fourteen circulating fans that will provide 1,800 CFM, and four cooling fans (4CFM).

Small package evaporative coolers have a fan and evaporative pad in one box to evaporate water, which cools air and increases humidity. Heat is removed from the air to change water from liquid to vapor. Moist, cooler air enters the greenhouse while heated air passes out through roof vents or exhaust louvers. The evaporative cooler works best when the temperature of the outside air is low. The cooler air can be used without water evaporation to provide the ventilation of the greenhouse. See the evaporative cooler capacity at 1.0 to 1.5 times the volume of the greenhouse. An alternative system, used in commercial greenhouses, places the pads on the air inlets or air out of the greenhouse and uses the exhaust fans on the other end of the greenhouse to pull the air through the house.

Watering Systems

A water supply is essential. Hand watering is acceptable for most greenhouse crops if someone is available when the task needs to be done; however, many hobbyists work away from home during the day. A variety

Controllers/Automation

Automatic control is essential to maintain a reasonable environment in the greenhouse. On a winter day with varying amounts of sunlight and clouds, the temperature can fluctuate greatly. Close supervision would be required if a manual ventilation system were to be used. Therefore, unless close monitoring is possible, both hobbyists and commercial operators should have automated systems with thermostats or other sensors.

Thermostats can be used to control individual units, or a central controller with one temperature sensor can be used. In either case, the sensor or sensors should be shaded from the sun, located about plant height away from the sidewalls, and have constant airflow over them. An aspirated box is suggested; the box houses each sensor and has a small fan that moves greenhouse air through the box and over the sensor (Figure 5). The box should be painted white so it will reflect solar heat and allow accurate readings of the air temperature.

Figure 5. Thermostats in the middle of the greenhouse.

Watering Systems

A water supply is essential. Hand watering is acceptable for most greenhouse crops if someone is available when the task needs to be done; however, many hobbyists work away from home during the day. A variety